

1 050597

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,866 - 0000

Approx. NW, NE, EC, 30, T 34 S, R 34 W/X

4726 feet from S section line

1874 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Woodman 'C' Well # 1

Operator: Petroleum, Inc.

County Seward 217.43
(Zone N/A)

Name & Address 300 West Douglas, Suite 800

Well Total Depth 6690 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1662

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Rine Drilling Company License Number 6059

Address 300 West Douglas, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 29 Month: July Year: 1985

Plugging proposal received from Steve Phillips

(company name) Petroleum, Inc. (phone) 316-624-1686

Elevation 2956 GL

were: to fill hole with heavy mud and spot cement through drill pipe 2968 KB

1st plug at Hugoton and Council Grove with 100 sx cement Anhydrite N/A

2nd plug 30' out of surface pipe with 50 sx cement

3rd plug at 800' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 am Day: 29 Month: July Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement, 2nd plug at 1662' with 50 sx cement, 3rd plug at 800' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel.
(If additional description is necessary, use BACK of this form.)

INVOICED

(Do not) observe STATE PLUGGING COMMISSION

DATE 8-14-85

AUG 14 1985

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 9608

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84