

1100248

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-20,857 ~~0000A~~
C NW NW SEC. 28, T 34 S, R 34 W

10-19

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BLASER WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 221.58

OPERATOR LICENSE # 5941

WELL TOTAL DEPTH 6800 FEET

OPERATOR: ROSEL ENERGY, INC

PRODUCTION CSG: SIZE 4 1/2" @ 4615' WITH 225 SX

NAME AND 302 S CLAY

SURFACE CASING: SIZE 8 5/8" @ 1664' WITH 490 SX

ADDRESS LIBERAL, KS 67901

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING SERVICE LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 19 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM HAROLD FRAULI

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 2680-3007

1ST PLUG SET CIBP AT 2660 WITH 2 SX CEMENT ON TOP.

2ND PLUG AT 1690' WITH 50 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT.

4TH PLUG AT 40'-0' WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 4:30 AM DAY: 19 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 2660' WITH 2 SX CEMENT ON TOP.

2ND PLUG AT 1690' WITH 50 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT.

4TH PLUG AT 40'-' WITH 15 SX CEMENT.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1725' OF 4 1/2" CASING. RUN FREEPOINT BY ROSEL. MARKER DEPTH AT 1568'.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

RECEIVED
KANSAS CORP COM
1998 NOV -5 12:59

11-5-98
60266

10-19 JAN 29 1999