

To: 1 020462 5-6 API NUMBER 15-175-21,204-00-00 8P  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App. SE NW NW, SEC. 23, T. 34 S, R. 34 W/EK  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6120 Lease Name Stevesson Well # 2-23  
Operator: Cabot Oil & Gas Corporation County Seward 94.32  
Name & Address 9400 N. Broadway, Suite 608  
Oklahoma City, OK 73114 Well Total Depth 2902 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 793

Abandoned Oil Well            Gas Well X Input Well            SWD Well            D&A             
Other well as hereinafter indicated           

Plugging Contractor Cabot Oil & Gas Corp. License Number 6120  
Address 9400 N. Broadway, Ste. 608, Oklahoma City, OK 73114  
Company to plug at: Hour: 8:30 a.m. Day: 6 Month: 5 Year: 19 92

Plugging proposal received from Carl Cowan  
(company name) Cabot Oil & Gas Corp. (phone) 405-478-6514  
were: 4 1/2" at 2888' w/550 sx cement, PBSD 2835', Perfs at 2648-55, 2680-87; 2716-36'

1st plug set CIBP at 2604' with 2 sx cement on top with bailer,  
2nd plug run tubing, circulate hole with mud, and pump 20 sx cement at 1695-1450',  
3rd plug pump 20 sx cement at 880-650',  
4th plug pump 10 sx cement at 90 to -4'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part            None             
Operations Completed: Hour: 2 p.m. Day: 6 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2604' with 2 sx cement on top with bailer,  
2nd plug ran tubing, circulated hole with mud and pumped 20 sx cement at 1695-1450',  
3rd plug pumped 20 sx cement at 880-650',  
4th plug pumped 10 sx cement at 90 to -4'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.  
(if additional description is necessary, use BACK of this form)

INVOICED  
MAY 21 1992  
DATE             
INV. NO. 35302

Signed Glenn R Barlow  
(TECHNICIAN)

RECEIVED  
MAY 8 1992  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS