

1 030625

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,889 - 0000

NW NW , SEC. 21 , T 34 S, R 34 (W) EX
4620 feet from (S) section line
4620 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Hacker Trust Well # 'C' 1

Operator: Petroleum, Inc.
Name & Address 300 West Douglas, Suite 800
Wichita, KS 67202

County Seward

Well Total Depth 6750 St. Louis 219.3' feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1674

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P. O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 11:30 am Day: 20 Month: December Year: 19 85

Plugging proposal received from Steve Phillips

(company name) Cheyenne (phone) 316-277-2062
Elevation 2954 KB

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1666'

1st plug at 3000' with 40 sx cement 2nd plug at 2630' with 40 sx cement

3rd plug at 1680' with 40 sx cement 4th plug at 750' with 30 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole with 10 sx cement

8th plug to circulate mouse hole with 10 sx cement. Plug water well from bottom to top
with cement Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 pm Day: 20 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3000' with 40 sx cement, 2nd plug at 2630' with 40
sx cement, 3rd plug at 1680' with 40 sx cement, 4th plug at 750' with 30 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole with 10 sx

cement, and plugged water well from bottom to top with cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 27 1985

INV. NO. 11753

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1985

Signed Steve Durrant
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84