

1100258

PH

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-20,870-0000
SW SW NW SEC. 20, T 34 S, R 34 W

10-27

CONSERVATION DIVISION - PLUGGING SECTION 3140 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME IMBLER WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 216.13

OPERATOR LICENSE # 5941

WELL TOTAL DEPTH 6650 FEET

OPERATOR: ROSEL ENERGY, INC PRODUCTION CSG: SIZE 4 1/2" @ 6649' WITH 190 SX

NAME AND 302 S CLAY SURFACE CASING: SIZE 8 5/8" @ 1670' WITH 700 SX

ADDRESS LIBERAL, KS 67901

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR ALLIED CEMENTING SERVICE LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 27 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM HAROLD FRAULI

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 3172'-2784' MARKER DEPTH: ANHYDRITE @ 1630' FROM LOG

1ST PLUG SET CIBP AT 2650' WITH 2 SX CEMENT ON TOP WITH DUMPBAILER.

2ND PLUG AT 1700' WITH 50 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT.

4TH PLUG AT 40'-0' WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 27 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT _____

1ST PLUG SET CIBP AT 2650' WITH 2 SX CEMENT ON TOP WITH DUMPBAILER.

2ND PLUG AT 1700' WITH 50 SX CEMENT.

3RD PLUG AT 650' WITH 50 SX CEMENT.

4TH PLUG AT 40'-0' WITH 15 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1715' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters
(TECHNICIAN) FORM CP-2/3

Signature

RECEIVED
KANSAS CORP COM
JAN 29 1999

11-5-98
60266

10-27

JAN 29 1999