

To: 1 020746 3-7  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,755-0000  
150' S of  
SE SW, SEC. 19, T. 34 S, R. 34 WXX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3744  
Operator: JMA Resources, Inc.  
Name & Address 5400 N. Grand Blvd., Ste. 305  
Oklahoma City, OK 73112

510 feet from S section line  
3300 feet from E section line  
Lease Name Roy Green Well # 2-19  
County Seward  
Well Total Depth 6759 219.66 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 1728 feet

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 4 Month: 3 Year: 19 94

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling (phone) 316-624-7455

Work: 5 1/2" at 6701' w/300 sx cement, PBSD 6485', Perfs at 6462-6514, 6226-44'

1st plug pump 1 sx hulls and 20 sx cement at perfs, displace with mud.

2nd plug pump 35 sx cement at 2500', 3rd plug pump 50 sx cement at 1750',

4th plug pump 40 sx cement at 700', 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6 p.m. Day: 7 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, displaced with mud,

2nd plug pumped 35 sx cement at 2500',

3rd plug pumped 50 sx cement at 1750',

4th plug pumped 40 sx cement at 700',

5th plug ran 10 sx cement at 40 to -7'. All plugs displaced with mud.

Remarks: Used common cement by Sargent's. Recovered 2634' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

DATE 3-22-94 XXXXXX observe this plugging.

INVOICED  
DATE 40140  
INVT. NO. 3-7

Signed Glenn R. Barlow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 16 1994  
CONSERVATION DIVISION  
Wichita, Kansas