

1 020329

8-31

315

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
700 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,688-0000

NE NE NE, SEC. 11, T 34 S, R 31 W/E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Black Well # 1

Operator: Kaiser-Francis Oil Company

County Seward 198.25

Name & Address P.O. Box 21468

Well Total Depth 6100 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1518

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Reeves Casing, Inc. License Number 3003

Address P.O. Box 94204, Oklahoma City, OK 73143

Company to plug at: Hour: 10 a.m. Day: 30 Month: 8 Year: 19 90

Plugging proposal received from Johnny Gooden

(company name) Reeves Casing, Inc. (phone) 405-677-8347

were: 5 1/2" at 6099' w/300 sx cement, PBTD 5000', Perfs at 4336-48'

1st plug set CIBP at 4300' with 3 sx cement on top,

2nd plug pump 50 sx cement at surface casing,

3rd plug pump 40 sx cement at 800',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 5:30 p.m. Day: 31 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4300' with 3 sx cement on top, loaded hole with mud, 2nd plug pumped 50 sx cement at 1540-1400',

3rd plug pumped 40 sx cement at 800-680',

4th plug pumped 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 3700' of 5 1/2" casing. Used Class H cement by Western.
(if additional description is necessary, use BACK of this form.)

INVOICED ~~XXXXXX~~ observe this plugging.

Signed Glen R. Barber
(TECHNICIAN)

DATE 9-14-90

INV. NO. 29305

8-31