

1050152

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW NW, SEC. 10, T 34 S, R 29 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,614 -00-00

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5021

Lease Name Laraby Well # 1-10

Operator: Imperial Oil Company

County Meade

Name & Address 720 Fourth Financial Center

Well Total Depth 5930 ^{192.72} feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1620

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 am Day: 22 Month: February Year: 19 84

Plugging proposal received from Norman Voth

(company name) kelso (phone) 316-938-2457

were: 5 1/2 set at 5929 PBTB 5903 Perfs 5755-58

1st plug pumped 35 sx cement to bottom and spotted plug

2nd plug squeezed through head with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped additional 125 sx cement.

Maximum pressure 100# and shut-in pressure 100#

Luthi gave the orders Lacey saw the operation
Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:20 pm Day: 22 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 5929 PBTB 5903 Perfs 5755-58

1st plug pumped 35 sx cement to bottom and spotted plug

2nd plug squeezed through head with 3sx hulls, 15 sx gel, 50 sx cement, 15 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped additional 125 sx cement.

Maximum pressure 100# and shut-in pressure 100#

Remarks: Use 60/40 Pozmix 2% gel 3% cc. by Halliburton They recovered 4317' of 5 1/2"
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 3-5-84

FEB 29 1984

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 0523

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84