

1100234

TO: STATE CORPORATION COMMISSION

8-25

API NUMBER 119-20,964-0000  
SE SE SE SEC. 8, T 34 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 380 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 380 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WYNONA A TRUST WELL # 1-8

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 204.75

OPERATOR LICENSE # 30129 WELL TOTAL DEPTH 6300 FEET

OPERATOR: EAGLE CREEK CORPORATION PRODUCTION CSG: SIZE 4 1/2 " FEET 5433

NAME AND 107 N MARKET #411 SURFACE CASING: SIZE 8 5/8" FEET 1587'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING LICENSE NUMBER 31151

ADDRESS RT 1 BOX 49BA, TYRONE, OK 73951

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 21 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING (PHONE) 580-854-6515

WERE: PERFS AT 5048 TO 5058

1ST PLUG PUMP 20 SX CEMENT & 200# HULLS FROM 5048' TO 4848'

2ND PLUG AT 1620' WITH 50 SX CEMENT

3RD PLUG AT 660' WITH 25 SX CEMENT

4TH PLUG AT 40'- 0' WITH 10 SX CEMENT

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 25 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG PUMPED 20 SX CEMENT & 200# HULLS FROM 5048' TO 4848'

2ND PLUG AT 1620' WITH 50 SX CEMENT

3RD PLUG AT 660' WITH 25 SX CEMENT

4TH PLUG AT 40' - 0' WITH 10 SX CEMENT

REMARKS: USED COMMON CEMENT BY HORTON. RECOVERED 2617' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

(I DID NOT) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

RECEIVED  
KANSAS CORP COM  
SEP 04 1998

INVOICED

DATE SEP 04 1998

INV. NO. 51262