

To: 1 020368  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-10  
API NUMBER 15- 175-20,503 - 0000226 R

C. NW, SEC. 35, T. 34 S, R. 31 W/R  
3960 feet from S section line  
3960 feet from E section line  
Lease Name Federal Land Bank Well # 1  
County Seward 201.50  
Well Total Depth 6200 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1598

TECHNICIAN'S PLUGGING REPORT

Operator License # 7123  
Operator: H.I., Inc.  
Name  
Address P.O. Box 2526  
Liberal, KS 67905-2526

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 8 Month: 4 Year: 19 91

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 6200' w/400 sx cement, Perfs at 5242-48, 6160-67'  
1st plug pump 1 sx hulls and 20 sx cement, 20 bbl. mud, 1/2 sx hulls, and 20 sx cement,  
2nd plug pump 50 sx cement at 1630',  
3rd plug pump 30 sx cement at 700',  
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour 5:30 p.m. Day: 10 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls, 20 sx cement, 20 bbls. mud, 1/2 sx hulls and 20 sx cement. Pressure 1000#.

2nd plug pumped 50 sx cement at 1630',

3rd plug pumped 30 sx cement at 700',

4th plug pumped 10 sx cement at 40 to -4'.

Mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 2570' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

(If you wish to observe this plugging.)

INVOICED

DATE 4-22-91

INV. NO. 31630

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1991  
CONSERVATION DIVISION  
Wichita, Kansas