

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-~~175 20458~~-0000

CSW Sec. 28, T 34 S, R 31 WE

TECHNICIAN'S PLUGGING REPORT

Operator License # 5701

Operator: NATIONAL OIL CO.  
Name & Address 1350 17th  
Suite 200  
Drew Co 80202

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

Lease Name Long Well # 1

County Seward

Well Total Depth 6050' feet \$196.62

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1527'

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506 Liberal Ks. 67901

Company to plug at: Hour: 9:00 AM Day: 20 Month: 4 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bib Sargent

(company name) \_\_\_\_\_ (phone) 624-7455

were: 4 1/2" @ 6058 w/100 sf Perfor @ 5936-96 - Rec. 3211'  
of casing -

plug bottom w/ 25.5x cement + plug to 5800'

Plug through 4 1/2" on way-out hole -

1st plug @ 1525' w/25 sf

2nd " @ 840' w/15 sf

3rd Solid Plug - full plug @ 40' -> cnt to 0' w/100 sf  
Signed Steve Drummond  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2:00 PM Day: 21 Month: 4 Year: 1983

ACTUAL PLUGGING REPORT

plugged as ordered

RECEIVED  
STATE CORPORATION COMMISSION

APR 26 1983

Remarks: \_\_\_\_\_

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 5-10-83  
INV. NO. 4247-W

Signed Steve Drummond  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

# K. G. S. LIBRARY WELL LOG

COMPANY National Oil Co.

SEC. 28-34-31W

FARM Long

NO. 1

LOC. C SW/4


TOTAL DEPTH 6060'

COUNTY Seward

COMM. 10/07/80

COMP. 10/21/80

CONTRACTOR Zenith Drilling Corporation



Ran 38 jts. new 24#, 8 5/8" csg., set at 1527' with 900 sacks cement

Ran 148 jts. new 10.5#, 4 1/2" csg., set at 6057 with 200 sacks cement

ELEVATION 2718 KB

PRODUCTION 2706 GL

FIGURES INDICATE BOTTOM OF FORMATIONS

582	Sand
1528	Sand and Red Bed
2150	Shale
5545	Lime & Shale
5630	Lime
6060	Lime & Shale

State of KANSAS  
County of SEDGWICK } ss

I, Emmet E. Hall of Zenith Drilling Corporation

upon oath state the above and foregoing is a true and correct copy of the log of the Long #1 well.

Subscribed and sworn to before me this 27th day of October, 1980

My Commission Expires: 12/15/80

Sharon R. Allen, NOTARY PUBLIC  
STATE CORPORATION COMMISSION

APR 21 1983

CONSERVATION DIVISION  
Wichita, Kansas