

To: 1100199 2-19  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 175-20,459-0000  
C SW NW, SEC. 28, T 34 S, R 31 W/E  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 9262  
Operator: Lowry Exploration, Inc.  
Name & Address: P.O. Box 1847  
Liberal, KS 67905-1847

Lease Name Wood Well # 1  
County Seward 201.50  
Well Total Depth 6200 feet  
Conductor Pipe: Size          feet  
Surface Casing: Size 8 5/8 feet 1463

Abandoned Oil Well          Gas Well X Input Well          SWD Well          D&A           
Other well as hereinafter indicated         

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12 p.m. Day: 18 Month: 2 Year: 19 98

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 6073'=100 sx cement, PBTD 6037', Perfs at 5934-38, 5940-62'  
1st plug pump 2 sx hulls and 20 sx cement on bottom,  
2nd plug spot 50 sx cement at 1500', displace with mud,  
3rd plug spot 40 sx cement at 650', displace with mud,  
4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Gary Winters  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part          None         

Operations Completed: Hour: 4:30 p.m. Day: 19 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug pump 2 sx hulls and 20 sx cement at 5934-5734',  
2nd plug spotted 50 sx cement at 1500', displaced with mud,  
3rd plug spotted 40 sx cement at 650', displaced with mud,  
4th plug at 40-0' with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 25 1998

Remarks: Used common cement by Sargent & Horton. Recovered 2823' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(Please observe this plugging.)

DATE FEB 26 1998

Signed Gary Winters  
(TECHNICIAN)

INV. NO. 50160  
2-19