

9-20-87

1 061015

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,968 -0000

NW NW SE, SEC. 5, T 34 S, R 33 W/E  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Fitzgerald Well # 1-5

Operator: Donald C. Slawson  
Name & Address: 20 North Broadway, Suite 700  
Oklahoma City, OK 73102

County Seward 209.63

Well Total Depth 6450 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1550

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Slawson Drilling Company, Inc. License Number 5657

Address 200 Douglas Bldg, 104 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 19 Month: 9 Year: 19 87

Plugging proposal received from Brad Nash

(company name) Slawson Drilling Company, Inc. (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1580'

1st plug 3080' with 175 sx cement, 2nd plug at 1580' with 60 sx cement, 3rd plug at 750' w/35 sx

4th plug at 40-0' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:15 a.m. Day: 20 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 3080' with 175 sx cement,

2nd plug at 1580' with 60 sx cement,

3rd plug at 750' with 35 sx cement,

4th plug at 40-0' with 12 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Western.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
You will observe this plugging.

Signed Paul Luthi (TECHNICIAN)

DATE 10-7-87

INV. NO. 18402 OCT 29 1987