

To: 1 020449
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-7 API NUMBER 15-175-20,989-0001 772
SW NE NE, SEC. 4, T. 34 S, R. 33 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: OXY USA Inc.

Name: P.O. Box 26100

Address

Oklahoma City, OK 73126-0100

4030 feet from S section line

1100 feet from E section line

Lease Name Graham B Well # 2

County Seward

Well Total Depth 6550 212.87 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1699

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10:30 a.m. Day: 7 Month: 4 Year: 19 92

Plugging proposal received from Kirby Lillard

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 6549' w/1350 sx cement, PBD 2740', Perfs at 2649-87'

1st plug set CIBP at 2600' with 2 sx cement on top,

2nd plug shoot pipe at 2255', load hole with mud and pump 50 sx cement at 1730',

3rd plug pump 40 sx cement at 750',

4th plug pump 10 sx cement at 40-0',

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5 p.m. Day: 7 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2600' with 2 sx cement on top with bailer,

2nd plug shot pipe at 2255', loaded hole with mud and pumped 50 sx cement at 1730',

3rd plug pumped 40 sx cement at 750', displaced all plugs with mud,

4th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2255' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 5-5-92

INV. NO. 35/36

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1992
CONSERVATION DIVISION
Wichita, Kansas