

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21843-00-01
Spot: SWNW Sec/Twnshp/Rge: 2-34S-33W
1980 feet from N Section Line, 660 feet from W Section Line
Lease/Unit Name: FITZGERALD C Well Number: 1H
County: SEWARD Total Vertical Depth: 5140 feet

Operator License No.: 4549 Conductor Pipe: Size feet: #167.05
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1631
Address: 1201 LAKE ROBBINS DRIVE Production: Size 5.5 feet: 5140 WITH 430 SX CMT
THE WOODLANDS, TX 77380 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/31/2002 8:30 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & 400# HULLS ON BOTTOM. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/31/2002 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4290'. CIBP @ 4290'. PERFS AT 2602-69'. PUMPED DOWN 5 1/2" 400# HULLS & 25 SX CMT. 1ST PLUG PULLED CASING TO 1660' CIRCULATED HOLE WITH MUD & PUMPED 50 SX CMT. DISPLACED WITH 33 BBL MUD. 2ND PLUG PULLED CASING TO 550' & PUMPED 40 SX CMT. DISPLACED WITH 8 BBL MUD. 3RD PLUG TO 40' & PUMPED 10 SX CMT.

RECEIVED
JAN 09 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1909' OF 5 1/2 CASING.

Plugged through: CSG

District: 01

RECEIVED
JAN - 2 2003
KCC Dodge City

Signed Michael J Maier
(TECHNICIAN)

INVOICED
DATE 1-10-03
INV. NO. 2003061046

Form CP 2/3