

1100333

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-20,273 -00-00  
SE SW SEC. 36, T 34 S, R 32 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BIRD WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD

198.25

OPERATOR LICENSE # 31389

WELL TOTAL DEPTH 6100 FEET

OPERATOR: NOBLE PETROLEUM INC.

PRODUCTION CSG: SIZE 4 1/2" @ 5235' WITH 125 SX

NAME AND 3101 N ROCK ROAD #125

SURFACE CASING: SIZE 8 5/8" @ 1473' WITH 700 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT AND HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 17 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT AND HORTON PLUGGING (PHONE) 580-854-6515

WERE: PERFS AT 5022-41

1ST PLUG ON 2/17/00 PUMP 100# HULLS AND 20 SX CEMENT DISPLACE WITH MUD AT 500#.

2ND PLUG ON 2/18/00 REPLUG WITH ANOTHER 300# HULLS AND ADDITIONAL 15 SX CEMENT.

3RD PLUG SPOT 50 SX CEMENT AT 1500'. 4TH PLUG SPOT 40 SX CEMENT AT 650'.

5TH PLUG SPOT 10 SX CEMENT AT 40' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 18 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG ON 2/17/00 PUMP 100# HULLS AND 20 SX CEMENT DISPLACE WITH MUD AT 500#.

2ND PLUG REPLUG WITH ANOTHER 3003 HULLS AND ADDITIONAL 15 SX CEMENT.

3RD PLUG SPOT 50 SX CEMENT AT 1500'. 4TH PLUG SPOT 40 SX CEMENT AT 650'.

5TH PLUG SPOT 10 SX CEMENT AT 40' TO SURFACE.

RECEIVED STATE CORPORATION COMMISSION

MAR -2 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1630' OF 4 1/2" CASING. CONSERVATION DIVISION

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

DATE 3/3/00

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

INV. NO. 061389