

To: 100182

12-15

API NUMBER 15-175-21,103-0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. NE SW SE, SEC. 24, T 34 S, R 33 W/4
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / 4549

Lease Name Condit SW Unit Well / 1-3

Operator: Anadarko Petroleum Corporation

County Seward 208.65

Name & Address P.O. Box 351

Well Total Depth 6420 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1545

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 12 Month: 12 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Size: 5 1/2" at 6420' w/200 sx cement, PBDT 6366', Perfs at 6276-81, 6299-6305'

1st plug spot 25 sx cement with 4 sx hulls on bottom, displace with mud,

2nd plug spot 25 sx cement at 2600', displace with mud,

3rd plug spot 50 sx cement at 1570', displace with mud,

4th plug spot 40 sx cement at 650', displace with mud, 5th plug spot 10 sx cement at 40-0'.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 15 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug spotted 25 sx cement with 4 sx hulls at 6276-6076', displaced with mud,

2nd plug spotted 25 sx cement at 2600', displaced with mud,

3rd plug spotted 50 sx cement at 1570', displaced with mud,

4th plug spotted 40 sx cement at 650', displaced with mud,

5th plug spotted 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent & Horton. Recovered 2606' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 05 1998

INV. NO. 49814

12-15

Signed Gary Winters (TECHNICIAN)

DEC 24 1997