

To: 1 190111 4-4
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA Inc.
Name:
Address P.O. Box 300
Tulsa, OK 74102

API NUMBER 15- 175-20,262-0001 Docket #D-26,113-
W/2 SE, SEC. 17, T 34 S, R 33 v XX
1320 feet from S section line
1980 feet from E section line
Lease Name Brown C Well # 3
County Seward 214.66
Well Total Depth 6605 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1609

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☒ O&A ☐

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address

Company to plug at: Hour: 8 a.m. Day: 4 Month: 4 Year: 19 97

Plugging proposal received from Reed Wilson

(company name) Halliburton (phone) 316-629-3578

were: 5 1/2" at 6120' w/200 sx cement, Perfs at 6036-48, 4328-35'

1st plug set CIBPs at 6010 & 4260' with 2 sx cement on top of each,

2nd plug at 3100' with 100 sx cement,

3rd plug at 1660' with 50 sx cement,

4th plug at 800' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 8:30 p.m. Day: 4 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6010' with 2 sx cement on top, 2nd plug set CIBP at 4260' with 2 sx cement. Perforated at 2999-3004', 2nd plug pumped 120 sx cement,

displaced to 2999', 3rd plug shot at 2600', pumped 80 sx cement, displaced with gel,

4th plug pulled to 1667' and pumped 50 sx cement, displaced with gel,

5th plug pulled to 807', pumped 50 sx cement, displaced with gel,

6th plug pulled to 40' and filled to surface with 10 sx cement.

Remarks: Used Hallilite cement by Halliburton. Recovered 2591' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
(old / XXXXXX) observe this plugging.

DATE 4-10-97

INV. NO. 47902

4-4 JUN 17 1997

Signed Gary Winters (TECHNICIAN)