

1 020373

4-26

417 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- 175-21,086-0000

NE SW SW, SEC. 15, T. 34 S, R 33 W/E  
1250 feet from S section line  
4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447  
Operator: OXY USA INC  
Name & Address: P O BOX 26100  
OKLAHOMA CITY OK 73126-0100

Lease Name Eubank Well # D-2  
County Seward 217.75  
Well Total Depth 6700 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1769

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor OXY USA License Number 5447  
Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 3:30 p.m. Day: 25 Month: 4 Year: 19 91

Plugging proposal received from Bill Smith

(company name) OXY USA (phone) 316-675-2293

Work: 5 1/2" at 2799' w/275 sx cement, PBTD 2756', Perfs at 2614-22, 2639-48, 2672-96'  
1st plug set CIBP at 2950',  
2nd plug fill hole with 9# mud, spot 30 sx cement at 1869',  
3rd plug at 800' with 50 sx cement,  
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 26 Month: 4 Year: 1991

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2580',  
2nd plug load hole with heavy mud, pumped 30 sx cement at 1870-1630' with tubing,  
3rd plug spotted 50 sx cement at 800-415',  
4th plug pumped 10 sx cement from 70-0'.

RECEIVED STATE CORPORATION COMMISSION

MAY 06 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used Class H cement by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Shawn R. Barlow (TECHNICIAN)

DATE 5-13-91

INV. NO. 31791