

2-17-88

128
R

1020121

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,304-0000
C SE SE, SEC. 13, T 34 S, R 33 W/E
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Condit Unit Well # 5-5

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

County Seward 209.63
Well Total Depth 6450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1595

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 2 P.m. Day: 15 Month: 2 Year: 19 88

Plugging proposal received from Doug Blair

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 6450' PBTB 6407' Perfs at 6270-85' Elevation 2809' GL TOC 5200'

1st plug pump 1 sx hulls and 25 sx common cement.

2nd plug pump 30 sx cement at 2570',

3rd plug pump 50 sx cement at 1648',

4th plug pump 25 sx cement at 700', 5th plug pump 10 sx cement at 35-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 17 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx common cement to perfs.

Load hole with mud,

2nd plug ran 30 sx cement at 2570',

3rd plug pumped 50 sx cement at 1648',

4th plug pumped 25 sx cement at 700',

5th plug pumped 10 sx cement at 35-0'.

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1988
2-23-88
Conservation Division
Wichita, Kansas

Remarks: Used common cement by Sargents. Recovered 2600' of 5 1/2" casing.

(Additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 2-26-88

Signed Glenn R. Barlow
(TECHNICIAN)

INV. NO. 19900

2-17 MAR 24 1988