

2-26-88 15-175-30003-0000
15-175-30003-0000

Docket #E-16,786

API NUMBER 15-Drill Completion 2/3/65

C NE NE, SEC. 13, T 34 S, R 33 W/EX

4620 feet from S section line

660 feet from E section line

Lease Name Condit Unit Well # 5-2

County Seward 207.19

Well Total Depth 6375 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1609

To: 1 020123
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation

Name & Address P.O. Box 351

Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: _____ Day: 24 Month: 2 Year: 19 88

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 6375' PBD 6324' Perfs at 6268-86' Elevation 2821'GL Est. TOC 5450'

1st plug pump 2 sx hulls and 25 sx cement, 2nd plug on stub with 30 sx cement,

3rd plug at 1650' with 50 sx cement, 4th plug at 700' with 25 sx cement,

5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 26 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement behind 1 1/2 sx hulls, displace 100 bbl.

mud and pressured up,

2nd plug ran 50 sx cement at 1395',

3rd plug ran 30 sx cement at 650',

4th plug ran 15 sx cement from 40-0'.

Could not get shot below 1417', pressured to 500 lbs., held good.

Remarks: Used common cement by Sargent's. Recovered 1400' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 3-4-88

INV. NO. 20008

Signed Steven R. Barlow
(TECHNICIAN)

2-26 MAR 24 1988

FORM CP-2/3
Rev.01-84

STATE CORPORATION COMMISSION
3-4-88
SEARCHED
INDEXED
SERIALIZED
FILED

INVOICED