

To: 1 090305 7-16  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,322-00-00  
50' W of  
S/2 SE, SEC. 14, T. 34 S, R. 34 W ~~XX~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 9953  
Operator: Harris Oil & Gas Company  
Name & Address 410 17th St., Ste. 2310  
Denver, CO 80202

660 feet from S section line  
1370 feet from E section line  
Lease Name Reiss Well # 1-14  
County Seward  
Well Total Depth 6700 219.75 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1642

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418  
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: \_\_\_\_\_ Day: 16 Month: 7 Year: 19 93  
Plugging proposal received from Harold Frauley  
(company name) Allen Drilling Co. (phone) 316-793-5681

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1650'  
1st plug at 2500' with 100 sx cement, 2nd plug at 1680' with 50 sx cement,  
3rd plug at 700' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 5:20 p.m. Day: 16 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2500' with 100 sx cement,  
2nd plug at 1680' with 50 sx cement,  
3rd plug at 700' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1993  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
I (X) ( ) did not observe this plugging.  
DATE AUG 04 1993  
INV. NO. 38244

Signed [Signature]  
(TECHNICIAN)