

1100315

TO:  
STATE CORPORATION COMMISSIONAPI NUMBER 15-175-21,780-0000  
20'S N/2 NW NW SEC. 13, T 34 S, R 34 WCONSERVATION DIVISION - PLUGGING SECTION 350 FEET FROM NORTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KEATING WELL # 1-13A

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 216.13OPERATOR LICENSE # 3988WELL TOTAL DEPTH EST. 6650 FEETOPERATOR: SLAWSON EXPLORATION CO., INC PRODUCTION CSG: SIZE        " FEETNAME AND 200 N HARVEY, SUITE 1412 SURFACE CASING: SIZE 8 5/8 " @ 1650' WITH SXADDRESS OKLAHOMA CITY, OK 73102ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL        D/A XOTHER WELL AS HEREINAFTER INDICATED       PLUGGING CONTRACTOR BIG A DRILLING LICENSE NUMBER 31572ADDRESS P.O. BOX 1856 LIBERAL, KS 67905-1856COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 21 MONTH: 09 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM DUANE(COMPANY NAME) BIG A DRILLING (PHONE) 316-624-1904

WERE: LOST 6 COLLARS AND BIT IN HOLE- SKIDDED RIG 10'. RE-DRILL AND LOST CIRCULATION ON  
2ND HOLE AT 205'. 1ST PLUG SPOT 40 SX CEMENT WITH 200# HULLS AT 205'. NO CIRCULATION.  
WAIT ON CEMENT 1 HOUR. 2ND PLUG SPOT 100 SX CEMENT NO CIRCULATION. WAIT ON CEMENT 1 HOUR.  
3RD PLUG SPOT 260 SX CEMENT. GOT CIRCULATION. LEFT HOLE FULL OF CEMENT. 4TH PLUG PUT 15  
SX CEMENT IN RAT HOLE THROUGH DRILL PIPE. 5TH PLUG PUT 10 SX CEMENT IN MOUSE HOLE THROUGH  
DRILL PIPE. PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART        NONE       OPERATIONS COMPLETED: HOUR: 9:30 PM DAY: 21 MONTH: 09 YEAR: 1999ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG SPOT 40 SX CEMENT WITH 200# HULLS AT 205'. NO CIRCULATION. WAIT ON CEMENT 1 HOUR.  
2ND PLUG SPOT 100 SX CEMENT NO CIRCULATION. WAIT ON CEMENT 1 HOUR. 3RD PLUG SPOT 260 SX  
CEMENT. GOT CIRCULATION. LEFT HOLE FULL OF CEMENT. 4TH PLUG PUT 15 SX CEMENT IN RAT HOLE  
THROUGH DRILL PIPE. 5TH PLUG PUT 10 SX CEMENT IN MOUSE HOLE THROUGH DRILL PIPE.

REMARKS: USED BLENDED CEMENT WITH 3% CC BY HALLIBURTON.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I DID NOT OBSERVE THIS PLUGGING.DATE 12/7/99  
INV. NO. 60944

SIGNED

Gary Winters  
(TECHNICIAN)CONSERVATION DIVISION  
Wichita, Kansas  
FORM CP-2/3

STATE CORPORATION COMMISSION

NOV 10 1999