

To: 1, 100183
STATE CORPORATION COMMISSION
Wichita, State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-17510150-8800
API NUMBER 15- Spud date 5/60
C SE, SEC. 10, T 34 S, R 34 W/EX
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name McGill Well # i-10
County Seward 209.72
Well Total Depth 6453 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1689

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12 p.m. Day: 18 Month: 12 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 6449' w/325 sx cement, PBD 6410', Perfs at 6345-6405'

1st plug pump 200 lbs. hulls and 20 sx cement on bottom,

2nd plug spot 25 sx cement at 2700', displace with mud,

3rd plug spot 50 sx cement at 1720', displace with mud,

4th plug spot 40 sx cement at 650', displace with mud, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 18 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement from 6250-6405',

Circulated with mud to surface. 2nd plug spotted 25 sx cement at 2700', displaced with mud,

3rd plug spotted 50 sx cement at 1720', displaced with mud,

4th plug spotted 40 sx cement at 650', displaced with mud,

5th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 2707' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JAN 05 1998
INV. NO. 49815
12-18

Signed Gary Winters (TECHNICIAN)