

1 090807

4-30

API NUMBER 15-175-20,628-0001

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

C NE NE, SEC. 7, T 34 S, R 34 W/X
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5941
Operator: Rosel Energy Inc.
Name & Address: 302 S. Clay
Liberal, KS 67901

Lease Name Seaton Well # 2
County Seward 104.94
Well Total Depth 3229 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1714

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 30 Month: 4 Year: 19 97
Plugging proposal received from Kirby Lillard

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

vera: 4 1/2" at 3229' w/225 sx cement, PBSD 3193', Perfs at 3102-37, possible perfs at 2600 or 2650'
1st plug set CIBP at 3000' with 2 sx cement on top, 2nd plug set CIBP at 2300' with 2 sx cement,
3rd plug at 1930' with 50 sx cement,
4th plug at 500' with 40 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 30 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3000' with 2 sx cement on top,
2nd plug set CIBP at 2300' with 2 sx cement on top,
3rd plug at 1750' with 50 sx cement,
4th plug at 600' with 40 sx cement,
5th plug at 40' with 10 sx cement.

RECEIVED
KANSAS CORP COMM
1997 MAY -6 P 1:01

Remarks: Used common cement by Sargents. Recovered 2025' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

DATE / old date observe this plugging.

DATE MAY 07 1997

Signed [Signature] (TECHNICIAN)

INV. NO. 48084

4-30