

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21046-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 36-34S-33W
3400 feet from S Section Line, 4680 feet from E Section Line
Lease/Unit Name: BOX Well Number: 2
County: SEWARD Total Vertical Depth: 6522 feet

Operator License No.: 7123
Op Name: H. I., INC.
Address: PO BOX 2526 1600 BLUEBELL RD.
LIBERAL, KS 67905

Production Casing Size: 4.5 feet: 6092 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 1612 WITH 600 SX CMT
\$211.97

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/17/2003 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (620) 624-8484

Proposed Plugging Method: CIBP @ 4890' WITH 2 SX CMT. PLUG AT 1630' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/18/2003 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 6092'. PERFS AT 6050-54'. SET CIBP @ 4890' WITH 2 SX CMT ON TOP. STACKED OUT WITH WIRELINE AT 4900'. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE TO 1630'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600' & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE WITH MUD & PUMP 10 SX CMT.

RECEIVED
MAR 24 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2022' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 3-25-03

INV. NO. 2003061325

Form CP-23