

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21116-00-00
Spot: SESWSW Sec/Twnshp/Rge: 36-34S-33W
330 feet from S Section Line, 4030 feet from E Section Line
Lease/Unit Name: BOX TWO THREE Well Number: 5
County: SEWARD Total Vertical Depth: 6669 feet

Operator License No.: 7123
Op Name: H. L. INC.
Address: PO BOX 2526 1600 BLUEBELL RD.
LIBERAL, KS 67905

Production Casing Size: 4.5 feet: 6594 WITH 375 SX CMT
Surface Casing Size: 8.625 feet: 1612 WITH 450 SX CMT
\$216.74

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/14/2003 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 5928' WITH 2 SX CMT. PLUG AT 1630' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/14/2003 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 6594'. PERFS AT 5990-6046'. SET CIBP @ 5928' WITH 2 SX CMT. 1ST PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 1630'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT.

RECEIVED
MAR 24 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2042' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 3-25-2003
INV. NO. 2003061325

Form 2/3