

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-01001-00-01
Spot: CNWSE Sec/Twnshp/Rge: 36-34S-33W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease/Unit Name: BOX (LANCASTER 1) Well Number: 1-R
County: SEWARD Total Vertical Depth: 5995 feet

Operator License No.: 7123
Op Name: H. I., INC.
Address: PO BOX 2526 1600 BLUEBELL RD.
LIBERAL, KS 67905

Production Casing Size: 4.5 feet: 5995 WITH 300 SX CMT
Surface Casing Size: 8.625 feet: 1550 WITH 923 SX CMT

\$194.84

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/13/2003 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 20 SX CMT & 300# HULLS ON BOTTOM. PLUG AT 1560' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/13/2003 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


CIBP @ 2650' WITH 3 SX CMT. PERFS AT 2620-28' & 5433-5437'. PUMP 300# HULLS & 20 SX CMT. LOAD HOLE. PRESSURE TO 500 PSIG. 1ST PLUG PULL OUT OF HOLE TO 1560'. LOAD HOLE & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCUALTION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT.

RECEIVED
MAR 24 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1739' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 3-25-03
INV. NO. 2003061325

Form CR128