

1020257

10-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-00376-0000

NE/4, SEC. 15, T. 33 S, R. 36 ~~W/4E~~

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Mueller Well # 1

Operator: Mobil Oil Corporation

County Stevens 91.88

Name & Address P.O. Box 5444

Well Total Depth 2827 feet

Denver, CO 80217

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 560

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mobil Oil Corporation License Number 5208

Address P.O. Box 5444, Denver, CO 80217

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 10 Year: 19 89

Plugging proposal received from Tommy Romero

(company name) Mobil Oil Corporation (phone) 316-544-5500

were: 7" at 2625' 5 1/2" at 1803' Elevation 3030' GL, 1175'-casing leak, 1803'-5 1/2" hook wall packer

1st plug pump 100 sx cement at 2577-2657 (50 sx above & below 7"),

2nd plug run tubing to 1853', pump 50' below hook wall packer, pump 28 sx cement to 1625',

3rd plug perforate at 610', circulate cement to surface

RECEIVED
STATE CORPORATION COMMISSION

NOV - 2 1989

Plugging Proposal Received by Steve Durrant

CONSERVATION DIVISION
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 25 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT Tagged bottom at 2516',

1st plug ran tubing to 1853', pump 30 sx cement at 1853-1625', pull tubing,

2nd plug perforate at 610', pump 26 barrels fluid, could not circulate, went on vacuum,

Ordered more cement and circulated to surface.

(10/24/89-Tagged tools lost in hole at 2771', pumped 20 bbls. gel w/5 sx hulls, formation took all. Pulled up to 2677', pumped 50 sx cement.)

Remarks: Used 50/50 Pozmix by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

Signed Steve Durrant
(TECHNICIAN)

DATE 11-3-89

INV. NO. 26348

10-25