

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20230-00-00  
Spot: SESENWNW Sec/Twnshp/Rge: 12-33S-41W  
1250 feet from N Section Line, 1250 feet from W Section Line  
Lease/Unit Name: EAGLEY A Well Number: 1  
County: MORTON Total Vertical Depth: 3360 feet

Operator License No.: 4549

Op Name: ANADARKO PETROLEUM CORPORATION

Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

Conductor Pipe: Size feet: 8/109.20

Surface Casing: Size 8.625 feet: 637

Production: Size 5.5 feet: 3360

Liner: Size feet:

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 01/03/2003 9:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed  
Plugging  
Method:

CIBP @ 2450' WITH 2 SX CMT. STUB PLUG WITH 50 SX CMT. 50 SX CMT AT 660'. 10 SX CMT AT 40'.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/03/2003 3:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:


CMT RETAINER AT 3150'. PERFS AT 2932-62'. CIBP @ 2450' WITH 2 SX CMT ON TOP. 1ST PLUG LOAD HOLE WITH MUD & PUMP 50 SX CMT AT 1100'. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 660'. LOAD HOLE AND PUMP 40 SX CMT. DISPLACE. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT TO SURFACE.

RECEIVED  
JAN 13 2003  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1116' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 1-14-03  
INV. NO. 2003061073