

To: 1 031289
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-27

15-129-30078-0000
API NUMBER 15- Docket #D-12,159

App: NE SE NW, SEC. 9, 7 33 S, R 41

3805 feet from S section line

2735 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Mills Well # 3D SWD

Operator: OXY USA INC.

County Morton

Name & Address P.O. Box 26100

Well Total Depth 1346 43.75 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size none feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X O&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Co. License Number 5866

Address 713 S. Simpson, Ulysses, KS 67880

Company to plug at: Hour: _____ Day: 21 Month: 6 Year: 19 94

Plugging proposal received from _____

(company name) _____ (phone) _____

Remarks: 4 1/2" at 1345' w/300 sx cement, PBD 1313', Perfs at 1204-20, 1224-28'

1st plug set CIBP at 1150' and dump 2 sx cement on top,

2nd plug at 1125' with 50 sx cement,

3rd plug at 500' with 50 sx cement to surface.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 22 1994

Plugging Proposal Received by Steve Durrant
WICHITA, KS
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: _____ Day: 27 Month: 6 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 1150' and dumped 2 sx cement on top,

2nd plug ran 2 3/8" tubing to 1120' and pumped 50 sx cement,

3rd plug at 558' with 40 sx cement,

4th plug at 93' with 10 sx cement,

Topped off with 1 sx cement.

Remarks: Used Class H cement by Gibson. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 8-24-94

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 40977