

To: 1 020466
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-3

API NUMBER 15- E-18,039 15-129-00158-00-01R
15-129-00158-099

SE SW SW, SEC. 9, T. 33 S, R. 41 W/E
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3408
Operator: Merrico Resources, Inc.
Name & Address: P.O. Box 849
Ardmore, OK 73402

Lease Name Berryman Richfield Unit Well # 22-1
County Morton 177.12
Well Total Depth 5450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1490

Abandoned Oil Well _____ Gas Well _____
Other well as hereinafter indicated _____
FNR INPUT Well X SWD Well _____ D&A _____

Plugging Contractor Sargent's Casing Pullers License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: _____ Day: 1 Month: 6 Year: 19 92

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 5 1/2" at 5330' w/175 sx cement, PBD 5293', Perfs at 5026-30'
1st plug set CIBP at 4950' with 2 sx cement on top,
2nd plug load hole with mud and pump 50 sx cement at 1530',
3rd plug pump 40.sx cement at 700',
4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: _____ Day: 3 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4950' with 2 sx cement on top,
2nd plug loaded hole with mud, pumped 50 sx cement at 1530',
3rd plug pumped 40 sx cement at 700',
4th plug pumped 10 sx cement at 40 to -4'.

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1992

Remarks: Used common cement by Sargent's. Recovered 2016' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I (operator) observed this plugging.

DATE 6-26-92
INV. NO. 35577

Signed Glenn R. Barlow
(TECHNICIAN)