

1 110008

API NUMBER 15- 129-20,770-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW NE , SEC.10 , T 33 S, R 41 W/E

4620 feet from S section line

1980 feet from E section line

Berryman Richfield

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Unit Well # 20-1

Operator: Ladd Petroleum Corporation

County Morton 167.70

Name & Address P. O. Box 2848

Well Total Depth 5160 Morrow feet

Tulsa, OK 74101-2848

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1399

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address 830 Sutton Place, Wichita, KS 67202

Company to plug at: Hour: 10:00 am Day: 28 Month: September Year: 19 85

Plugging proposal received from Ken Miller

(company name) Gabbert-Jones (phone) 316-263-6209

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3446 GL
solid bridge Anhydrite 1390-1750

1st plug at 5150' with 30 sx cement 5th plug hulls - plug at 40' -- cement to surface
with 10 sx cement

2nd plug at 3150' with 100 sx cement 7th plug to circulate rat hole with 10 sx cement

3rd plug at the base of the Anhydrite with 40 sx cement 8th plug to circulate mouse hole with 10 sx cement

4th plug at 700' with 35 sx cement

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 am Day: 28 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1560' with 40 sx cement, 2nd plug at 600' with 30 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Dowell
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

DATE 10-14-85

Signed James R. Kapp (TECHNICIAN)

INV. NO. 10448

OCT 14 1985

10-04-85

CONSERVATION DIVISION
Wichita, Kansas