

To: 1 020468 6-9
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-18,039
15-129-10588-0001 8 R

NW SW, SEC. 16, T. 33 S, R. 41 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3408

Lease Name Berryman-Richfield Well # 27-5
County Morton 177.12

Operator: Merrico Resources, Inc.
Name & Address: P.O. Box 849
Ardmore, OK 73402

Well Total Depth 5450 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1507

Abandoned Oil Well _____ Gas Well _____ ^{FNHR} Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2 p.m. Day: 4 Month: 6 Year: 19 92

Plugging proposal received from Kirby Lillard

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 5120' w/175 sx cement, PBTD 5092', Perfs at 5030-39, 5044-45'

1st plug shoot pipe at 2032', load hole with mud and pump 35 sx cement at 1530',

2nd plug pump 50 sx cement at 2000',

3rd plug pump 40 sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 9 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug tubing stub at 2100', shot pipe at 2032', loaded hole with mud and pumped 35 sx cement at 1530',

2nd plug pumped 50 sx cement at 2000',

3rd plug pumped 40 sx cement at 700',

4th plug pumped 10 sx cement at 40 to -7'.

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1992

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2032' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 6-26-92

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 35576