

1020891

7-25

15-129-10590-0000

To: STATE CORPORATION COMMISSION

API NUMBER 15- Drilled 1962

Wichita State Office Bldg. PLUGGING SECTION App. C SE NW, SEC. 16, T 33 S, R 41 W/8
130 S. Market, Room 2078
Wichita, KS 67202

3328 feet from S section line
3280 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3408

Lease Name Berryman Rich- Well # 25-2

Operator: TriPower Resources, Inc.

County field Unit Morton 166.56

Name & Address P.O. Box 849.

Well Total Depth 5125 feet

Ardmore, OK 73402

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1495

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

logs: 4 1/2" at 5124' w/150 sx cement, Perfs at 5030-35, 5042-46'

1st plug pump 1 sx hulls and 20 sx cement at perfs,

2nd plug pump 50 sx cement at 1527',

3rd plug pump 40 sx cement at 650',

4th plug pump 10 sx cement at 40 to -5'.

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1995

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 25 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs,

2nd plug pumped 50 sx cement at 1527',

3rd plug pumped 40 sx cement at 650',

4th plug pumped 10 sx cement at 40 to -5'.

Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 1527' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-8-95

INV. NO. 43260

7-25

Signed Glenn Barlow (TECHNICIAN)