

To: 1020892
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

7-31 15-129-00149-0000
API NUMBER 15- Spud date 6/5/62

SE NW NW, SEC. 16, T 33 S, R 41 W/R

4390 feet from S section line

4217 feet from E section line

Lease Name Berryman Richfield Unit Well # 25-1

County Morton 176.31

Well Total Depth 5425 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1467

TECHNICIAN'S PLUGGING REPORT

Operator License # 3408

Operator: TriPower Resources, Inc.

Name:

Address P.O. Box 849
Ardmore, OK 73402

Abandoned Oil Well Gas Well Input Well STD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address P.O. Box 49BA, Rt. 1, Tyrone, OK 73951-9731

Company to plug at: Hour: Day: 28 Month: 7 Year: 19 95

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 5 1/2" at 5328' w/125 sx cement, Perfs at 5001-5008, 5014-15, PBTD 5098'

1st plug pump 1 sx hulls and 25 sx cement down tubing,

2nd plug pump 50 sx cement at 1530',

3rd plug pump 40 sx cement at 650',

4th plug pump 10 sx cement at 40 to -5. Mud between all plugs.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 31 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement down tubing,

2nd plug pumped 50 sx cement at 1530',

3rd plug pumped 40 sx cement at 650',

4th plug pumped 10 sx cement at 40 to -5'.

Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 1534' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-8-95

INV. NO. 43259

7-31

Signed Glenn R Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

AUG 03 1995

STATE CORPORATION COMMISSION
WICHITA, KANSAS