

1 020004

API NUMBER 15- 175-20,832-0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE NE , SEC. 4 , T 33 S, R 34 W/4X
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Hitch Well # F-2

Operator: Anadarko Production Co.
Name & Address: P. O. Box 351
Liberal, KS 67901

County Seward 207.32

Well Total Depth 6379 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1645

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number 5287

Address P. O. Box 1598, Liberal, KS 67901

Company to plug at: Hour: 11:15 am Day: 12 Month: September Year: 19 85

Plugging proposal received from Jim Barlow

(company name) Anadarko (phone) 316-624-6253

were: 4 1/2" at 6379' PBTB 3025' Perfs at 2914-27' 2929-42' 2946-52' 4 1/2" with mud between
1st plug at 2850' with 50 sx cement

2nd plug at 1700' with 50 sx cement

3rd plug at 800' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:15 pm Day: 12 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement followed with heavy gel.

2nd plug at 1535' with 50 sx cement, 3rd plug at 800' with 50 sx cement, pushed down rubber
plug (8 5/8") to 40' and cemented to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985

Remarks: Recovered 1757' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED (If applicable) observe this plugging.

Signed Jim P. Barlow
(TECHNICIAN)

DATE SEP 24 1985

INV. NO. 10216