

To: 1 051380
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,467 - ~~0000~~

TECHNICIAN'S PLUGGING REPORT

W/2 SW, SEC. 23, T 33 S, R 37 W/E
1220 feet from S section line

Operator License # 5363

4620 feet from E section line

Operator: BEREXCO Inc.
Name & Address 970 Fourth Financial Center
Wichita, KS 67202

Lease Name J.R. Well # 1
County Stevens 221.00

Well Total Depth 6800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1725

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BEREDCO Inc. License Number 5147

Address 401 E. Douglas, #402, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 4 Month: 12 Year: 19 90

Plugging proposal received from Stan Wyckoff

(company name) BEREDCO, Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3000' with 100 sx cement, 2nd plug at 1760' with 50 sx cement,

3rd plug at 800' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11 p.m. Day: 4 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,

2nd plug at 1760' with 50 sx cement,

3rd plug at 800' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED
If (copy) / file note observe this plugging.

DATE 1-8-91

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 30399

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1990
12-21-90
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 11-18-90

PW

FORM MUST BE TYPED
FORM-C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL 189-21,467

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date
month day year

A/W/2 SW Sec 23 Twp 33 S, Rg 37 East West

OPERATOR: License # 5363
Name: BEREXCO INC.
Address: 970 Fourth Financial Center
City/State/Zip: Wichita, Kansas 67202
Contact Person: Evan Mayhew
Phone: (316) 265-3311

1220 feet from South line of Section
4620 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5147
Name: BEREDCO INC.

County: Stevens
Lease Home: J.R. Well #: 1
Field Name: Center, N.W.

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
 Gas ... Storage Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
Target Formation(s): Morrow
Nearest lease or unit boundary: 660
Ground Surface Elevation: 3100 feet MSL

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 585
Depth to bottom of usable water: 600
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 1750
Length of Conductor pipe required: 40
Projected Total Depth: 6800
Formation at Total Depth: St. Louis

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location:

Water Source for Drilling Operations:
 well ... farm pond ... other
DWR Permit #: Applied for
Will Cores Be Taken?: ... yes no
If yes, proposed zone:

Exp. 5/13/91

AFFIDAVIT

620' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with the provisions of the Act, et. seq.

It is agreed that the following minimum requirements will be met:

Pusher Ston
SPUD DATE 11-21-90 INIT. SD
LENGTH SURFACE PLANNED 1750 f
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 1725 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 6800 FORMATION
RAN PIPE @ SX DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ 3000 Ft. W/ 100 SX
Anhydrite Base @ 1760 Ft. W/ 90 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ 800 Ft. W/ 40 SX
Bottom Surface @ Ft. W/ SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIEG/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN R.L. DATE 12-14-90
TYPE OF CEMENT 60/40 per 6799A
STARTING TIME 7:00 (AM/PM) DATE 12-4-90
COMPLETION TIME 11:00 (AM/PM) DATE 12-4-90
CEMENT COMPANY Powell

RECEIVED
HAWWA
DEC 21 1990
CONSERVATION DIVISION
Wichita, Kansas

55-6-6