

To: 1 052171 9-29
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Completed 1940 15-189-00431
C SW NE, SEC. 30, T 33 S, R 37 ~~WXX~~ 0000

TECHNICIAN'S PLUGGING REPORT

Operator License / 4549
Operator: Anadarko Petroleum Corp.
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

3300 feet from S section line
2310 1980 feet from E section line
Lease Name Crawford A Well # 1
County Stevens 91.39
Well Total Depth 2812 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 559

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: _____ Day: 28 - Month: - 9 - Year: 1997

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 7" at 2546', Open hole 2546-2812'
1st plug pump 3 sx hulls and 40 sx cement to 2300', let set,
2nd plug at 600' with 70 sx cement,
3rd plug at 40' with 15 sx cement.

RECEIVED
KANSAS CORP. COMM
OCT-1 P 1:01

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12 p.m. Day: 29 - Month: 9 - Year: 1997

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 40 sx cement to 2300', tagged plug,
2nd plug at 500-350' with 70 sx cement, displaced with gel,
3rd plug at 40-0' with 15 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 500' of 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-2-97
INV. NO. 49184
9-29

Signed Richard M. Lacey
(TECHNICIAN)