

1 020220

2-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,201-0000

SW NE SE, SEC. 34, T 33 S, R 37 W/E

1390 feet from S section line

1200 feet from E section line

Lease Name Brubaker "A" Well # 4

County Stevens 149.50

Well Total Depth 4600 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1730

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Anadarko Petroleum Corporation License Number 4549

Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 2 Year: 19 89

Plugging proposal received from David Gilmore

(company name) Anadarko Petroleum Corporation (phone) 316-624-6253

were: 4 1/2" at 4600' PBTD 4550' Perfs at 4385-4406' TOC behind 4 1/2" at 1900'
TOC at 1900' on backside

1st plug spot 40 sx cement at 4550-4350', pump mud and hulls to 1800'

2nd plug spot 50 sx cement at 1600-1800',

3rd plug pump 35 sx cement at 700',

4th plug pump mud and hulls to 40' with 10 sx cement at 40-0'.

RECEIVED

STATE CORPORATION COMMISSION

MAR 07 1989

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 24 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug ran 40 sx cement at 4555-4335', Heavy mud to 3000',
open F.O. tool could not break circulation with tubing and packer,

2nd plug pumped 75 sx cement at 1800',

3rd plug mud to 750, pumped 35 sx cement at 750',

4th plug mud to 40', pumped 10 sx cement at 40-4' below ground level.

Remarks: Used Class H cement 2% cc by Halliburton. Recovered 1864' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 3-7-89

INV. NO. 24068

Signed [Signature] (TECHNICIAN)