

To: 1 110113  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003  
Operator: McCoy Petroleum Corporation  
Name & Address: 110 South Main, Suite 500  
Wichita, KS 67202

8-31 349 R  
API NUMBER 15-189-21,231-0000  
SW NW NE, SEC. 8, T 33 S, R 37 W/E  
4290 feet from S section line  
2310 feet from E section line

Lease Name Ratcliff Well # 1-8  
County Stevens 21450  
Well Total Depth 6600 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1734

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sweetman Drilling, Inc. License Number 5658  
Address 110 South Main, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 31 Month: 8 Year: 1988

Plugging proposal received from Eugene Salogna  
(company name) Sweetman Drilling, Inc. (phone) 316-265-5561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3121'  
Anhydrite 1711'  
1st plug at 3000' with 80 sx cement, 2nd plug at 1764' with 40 sx cement,  
3rd plug at 850' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 p.m. Day: 31 Month: 8 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 3000' with 80 sx cement,  
2nd plug at 1764' with 40 sx cement,  
3rd plug at 850' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 6 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (operator) did not observe this plugging.

DATE 9-8-88  
INV. NO. 22177

Signed James R. Kapp (TECHNICIAN)