

To: 1 **100210**
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API #15-189-004090000 ⁰⁰⁰¹ ← 15-189-00409-0001
API NUMBER 15- Spud date 8/24/30

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil E & P USA
Name: 2319 N. Kansas, P.O. Box 2173
Address: Liberal, KS 67905-2173

C NW, SEC. 8, T 33 S, R 37 ~~XX~~
3960 feet from S section line
3960 feet from E section line

Lease Name Ratcliff Well # 2
County Stevens 91.49
Well Total Depth 2815 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 12 1/2 feet 575

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 11 Month: 3 Year: 19 98

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 8 5/8" at 2503', PBD 2460', Perfs at 2540-2815', 6/46--25 sx cement spotted at 2460'
1st plug tag cement and circulate hole with mud, spot 100 sx cement at 600',
2nd plug pump 25 sx cement from 40-0'.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 11 Month: 3 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug tagged at 2297' with wireline, circulated hole with mud,
pulled out of hole with 8 5/8" to 600', spotted 100 sx cement,
2nd plug ran wireline, tagged cement at 475', pulled 8 5/8" out of hole, pumped 25 sx cement
at 40-0'.

Remarks: Used common cement by Sargent & Horton. Recovered 827' of 8 5/8"
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXXX~~) observe this plugging.

DATE 3-23-98

Signed Gary Winters
(TECHNICIAN)

INV. NO. 50285