

1 020352

2-14

207

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,352-0000

NE SE SW, SEC. 20, T 33 S, R 37 W/E

1250 feet from S section line

2690 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Roberts "A" Well # 1

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351

County Stevens 214.50

Well Total Depth 6600 feet

Liberal, KS 67905-0351

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1709

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Anadarko Petroleum Corp. License Number 4549

Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 1 p.m. Day: 14 Month: 2 Year: 19 91

Plugging proposal received from Junior Stuck

(company name) Anadarko Petroleum Corp. (phone) 316-544-7240

were: 4 1/2" at 6224', PBSD 6141', Perfs at 6082-6115', DV tool at 3206' cement to 1600'
1st plug set CIBP at 6030' and dump 2 sx cement on top,

2nd plug pump 30 sx cement at 1457-1357',

3rd plug pump 20 sx cement at 712-640',

4th plug pump 15 sx cement at 35-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 14 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6030' with 2 sx cement on top,

Load 4 1/2", run free point, back off at 1487',

2nd plug pumped 30 sx cement at 1457-1357',

3rd plug pumped 20 sx cement at 712-640',

4th plug pumped 15 sx cement at 35-0'.

RECEIVED STATE CORPORATION COMMISSION

FEB 21 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used Class H cement by Halliburton. Recovered 1487' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If desired, XXXXXX) observe this plugging.

DATE 2-25-91

INV. NO. 30874

2-14

Signed Glenn R. Barlow (TECHNICIAN)