

1060151

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189,20,701-0000

SW NW/4, SEC. 21, T 33 S, R 27 WXX

1980 feet from NXX section line

660 feet from WXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Shine "A" Well # 2

Operator: Anadarko Orodution Company

County Stevens

Name & Address Box 351

Well Total Depth 6350 206.37 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1706

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Johnson Drilling Co. License Number 7860

Address 3535 NW 58th Street, Oklahoma City, OK 73112

Company to plug at: Hour: 1:00 pm Day: 8 Month: February Year: 19 84

Plugging proposal received from Chuck Nelson

(company name) Anadarko (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1750' with 50 sx cement

2nd plug at 600' with 40 sx cement
solid bridge

3rd plug plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:00 pm Day: 8 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1750' with 50 sx cement, 2nd plug at 600' with 40 sx

cement, 3rd & 4th plugs - solid bridge - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10

sx cement.

Remarks: Use 60/40 Pozmix with 2% gel, 3% cc. by Halliburton. Luthi gave proposal and Clyde
(if additional description is necessary, use BACK of this form.)

Wiley saw the well plugged STATE CORPORATION COMMISSION
(did / ~~XXXXXX~~) observe this CONSERVATION COMMISSION

INVOICED

DATE 2-15-84

INV. NO. 0220

RECEIVED
FEB 13 1984

CONSERVATION DIVISION
Wichita, Kans

Signed Paul A. Luthi
(TECHNICIAN)