

To: 1 051473
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address: 2319 N. Kansas
Liberal, KS 67901

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address _____

Company to plug at: Hour: 9 a.m. Day: 19 Month: 9 Year: 1991

Plugging proposal received from Tommy Romero

(company name) Mobil Oil Corp. (phone) 316-544-5528

were: 5 1/2" at 6199' w/210 sx cement, PBTD 6070', Perfs at 5970-6050', 6084-6112'

1st plug set CIBP at 5965' w/2 sx cement on top.

2nd plug spot 95 sx cement from 3150-2460', pull 25 jts. tubing,

3rd plug spot 65 sx cement from 1800-1650', pull 9 jts. tubing,

4th plug spot 50 sx cement from 700-400', pull 11 jts. tubing, 5th plug spot 15 sx cement from 40-5'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11 a.m. Day: 20 Month: 9 Year: 1991

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5965' with 2 sx cement on top,

Hole in casing at 3365'.

2nd plug set tubing and packer at 2400' and pumped 250 sx cement,

3rd plug shot casing and spotted remaining plugs through casing:

1800' with 75 sx cement, 4th plug at 700' with 100 sx cement,

5th plug at 80' with 25 sx cement.

Remarks: Used 50/50 Pozmix by Halliburton. Recovered 1810' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 10-28-91

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 33486

9-20 NOV 20 1991

9-20 161
API NUMBER 15- 189-20,423 - 0000
C NE, SEC. 12, T 33 S, R 38 W/EX
3960 feet from S section line
1320 feet from E section line
Lease Name I.G. Ellis Well # 1-2
County Stevens 201.50
Well Total Depth 6200 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1712

RECEIVED
STATE CORPORATION COMMISSION
OCT 01 1991

CONSERVATION DIVISION
Wichita, Kansas