

15-175-20304-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-175-20,304-00-00 (of this well) 8/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM)            CONDIT UNIT            WELL NO. 5-5 WELL LOCATION C SE SE COUNTY Seward

SEC. 13 TWP. 34S RGE. 33  or  (W) TOTAL DEPTH 6450 PLUG BACK TD 6407

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO.           

SURFACE CASING SIZE 8-5/8" SET AT 1595 CEMENTED WITH 900 SACKS

CASING SIZE 5-1/2 SET AT 6450 CEMENTED WITH 200 SACKS

PERFORATED AT 6270-85

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill casing with hulls and mud to 6220 and dump 4 sacks cement on top of hulls and mud. Fill hole with mud to 5200, shoot off casing at freepoint and spot 30 sacks cement across csq cut. Spot 50 sacks cement 1645-1545 and spot 15 sacks cement from 40-0. Cap well.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Log Filed  
(If not, explain)            Driller's

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCOARDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION. RECEIVED

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Jerry Ruttman PHONE # (316) 624-6253 12-14-87  
CONSERVATION DIVISION  
Wichita, Kansas

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 6/88

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease  
(Operator or Agent)  
M. L. Pease Division Production Manager

DATE: 12/7/87

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH MCCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

December 17, 1987

MAR 17 '88

WELL PLUGGING NOTICE

EXPIRES

Condit Unit #5-5  
C SE SE  
Sec. 13-34S-33W  
Seward County

Anadarko Petroleum Corporation  
P. O. Box 351  
Liberal, KS 67905

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist  
Director  
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760