

15-175-30003-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-30003-00-00 completed 2/3/85 (of this well)

8/88

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) CONDT UNIT WELL NO. 5-2 WELL LOCATION C NE NE COUNTY Seward

SEC. 13 TWP. 34S RGE. 33 X(E) or (W) TOTAL DEPTH 6376 PLUG BACK TD 6324

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL X DOCKET NO. C-16,786

SURFACE CASING SIZE 8-5/8" SET AT 1609 CEMENTED WITH 850 SACKS

CASING SIZE 4-1/2" SET AT 6375 CEMENTED WITH 210 SACKS

PERFORATED AT 6276-80, 6268-76, 6280-85

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill casing with hulls and mud to 6218, dump 4 sacks cement on top of hulls and mud. Fill hole with mud to 3261, shoot off at freepoint and spot 30 sacks cement across casing cut. Spot 50 sacks cement 1659-1559 and spot 15 sacks cement from 40-0. Cap well.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Log Filed
(If not, explain) Originally filed under name of EUBANK "B" No.2

Driller's

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE # (316) 624-6253

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

DEC 14 1987

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)
M. L. Pease, Division Production Manager

DATE: 12/7/87

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
 KEITH R. HENLEY
 RICH KOWALEWSKI
 MARGALEE WRIGHT
 JUDITH McCONNELL
 FRANK A. CARO, JR.

GOVERNOR
 CHAIRMAN
 COMMISSIONER
 COMMISSIONER
 EXECUTIVE DIRECTOR
 GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI M. FEIST, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

THIS NOTICE
 MAR 17 '88
 EXPIRES

December 17, 1987
WELL PLUGGING NOTICE

Condit Unit #5-2 (SWD)
 C NE NE
 Sec. 13-34S-33W
 Seward County

Anadarko Petroleum Corporation
 P. O. Box 351
 Liberal, KS 67905

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

 Shari Feist
 Director
 State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760
