

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1518920558-00-00

LEASE NAME STEPHENS

WELL NUMBER 2-16

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 16 TWP. 33S RGE. 36 (E) or (W)

COUNTY STEVENS

Date Well Completed 7-17-1982

Plugging Commenced 6-20-2002

Plugging Completed 6-23-2002

RECEIVED

AUG 30 2006

KCC WICHITA

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-15-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation L MORROW Depth to Top 6064 Bottom 6082 T.D. 6200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
L MORROW	GAS	6064	6082	8 5/8	1682	0
				4 1/2	6199	1808

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PLUG 6064-6082 WITH 20 SXS CMT AND 3 SXS HULLS. SHOOT 4 1/2 CSG @ 1801. CIRCULATE MUD. PUMP 50 SXS CMT AT 1700-1550. PUMP 40 SXS CMT AT 600-480. PUMP 10 SXS CMT FROM 40 TO SURFACE. CUT OFF AND CAP 8 5/8 CSG 3 FT BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151


Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF ROTTER, ss.
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 26 day of August, 20 02

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

OR