

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-129-30078-0000

API NUMBER 15 NA

LEASE NAME Mills D

WELL NUMBER 3D

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

3805 Ft. from S Section Line

2545 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 9 TWP. 33SRGE. 41 (x) or (W)

ADDRESS P. O. Box 26100

COUNTY Morton

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 11/24/65

Character of Well SWD

Plugging Commenced 6/21/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/27/94

The plugging proposal was approved on 4/22/94 (date)

by Steve Durrant (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Glorieta Depth to Top 1204 Bottom 1228 T.D. 1345

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Glorieta	Oil	1204	1228	4 1/2	1345	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

RIH & set CIBP @ 1150. Dumped 2 sx cmt on top of CIBP. RIH w/2 3/8" tbq to 1120'. Mixed & pumped 50 sx Portland Class H cmt @ 1.18 Cu ft/sx & 15.0 PPG. POOH & laid down tbq to 558'. Mixed & pumped 40 sx Portland Class H @ 1.18 CU ft/sx & 15.8 PPG. POOH & laid down tbq to 93'. Cmt'd to surf w/ 10 sx Portland Type H cmt. Laid down remainder of tbq. (See Back of form)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Co License No. 05866

Address 1117 N Hwy 27, P. O. Drawer K, Elkhart, Ks 67950

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that they are true and correct, so help me God.

(Signature) *Jerry Ledlow*

(Address) P. O. Box 26100, OKC, OK 73126-0100


SUBSCRIBED AND SWORN TO before me this 19<sup>th</sup> day of August, 19 94

*Jeresa Addms*

Notary Public

My Commission Expires: May 6, 1998

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1994  
WICHITA, KANSAS



Topped off w/ 1 sx cmt. Cleaned up location.

