

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

RECEIVED
JAN 27 2003
KCC WICHITA

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-20230-00-00
API NUMBER 1512920230

LEASE NAME EAGLEY
WELL NUMBER A-1

TYPE OR PRINT
Fill out completely
and return to Cons. Div.
office within 30 days

4030 Ft. from S Section Line
4030 Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION
ADDRESS 701 S. TAYLOR, STE 400 AMARILLO, TX 79101
PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

SEC. 12 TWP. 33S RGE 41 (E) or ()
COUNTY MORTON

Character of Well GAS

Date Well Completed 2-1-1976

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 1-2-2003

Plugging Completed 1-4-2003

The plugging proposal was approved on RICHARD LACEY (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation WABAUNSEE Depth to Top 2932 Bottom 2962 T.D. 3360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
WABAUNSEE	GAS	2932	2962	8-5/8	637	0
				4-1/2	3360	1116

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. SET CIBP AT 2503. DUMP 2 SXS CMT ON CIBP. SHOOT OFF 4-1/2 CSG AT 1116. LOAD HOLE WITH MUD. SPOT 50 SXS CMT FROM 1100 TO 950. SPOT 50 SXS CMT FROM 660 TO 510. SPOT 10 SXS CMT FROM 40 TO 4. CUT OFF AND CAP 8-5/8 CSG.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address PO BOX 1598, LIBERAL, KS 67905-1598 PHONE: (316) 624-3879

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.


SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 22 day of January, 2000.

Lori Pearson
Notary Public



LORI PEARSON
Notary Public, State of Texas
My Commission Expires: 2/26/05

OK